

# Introduction Presentation **Design Goals Existing Conditions Community Feedback** Design **Phases of Work Cost Opinion** Q&A Meeting Agenda














Existing Conditions



#### June 2016 Altus Works Report

~Assessment of existing facility that identified deficiencies in life safety, accessibility, building mechanical, electrical and plumbing systems, repairs required to building envelope and site infrastructure


#### September 2018 Community Meeting


- ~Presented concepts for 2 new buildings and I repair option
- ~Community feedback indicated keeping the existing building with continued use during construction was a priority. Inclusion for the neighborhood's diverse age and ethnic backgrounds was very important.
- ~The gym, train display and dance studio were the most important core program spaces
- ~66% of attendees prefer repair of the existing building over a new facility.

#### February 2019 Community Meeting

- ~Presented 4 options: Existing building- limited remodel, Existing building-full remodel & addition, New building existing location and New building-new location.
- ~Community feedback: split between scope of remodel-Limited remodel (36%) and Full remodel & addition (35%).

 Based on commentary received during the community feedback process the overall preference is for the Remodeling options for the Fieldhouse.










**Existing Site Context Plan** 




Improved Drainage



Site Improvements Plan






**Ground Floor Plan** 




**Ground Floor - Lobby** 



**Ground Floor Plan** 



Ground Floor - Club Room




**Ground Floor Plan** 




Ground Floor - Gym



Ground Floor – Fitness Room




**Ground Floor Plan** 






Upper Floor – Club Room - Teen Lounge





Upper Floor – Dance Room







Upper Floor – Club Room



Upper Floor – Central Area







### **Building Section**



### **Entrance Addition View 1**



### **Entrance Addition View 2**




**Entrance Addition View 3** 



ANIMATION





Gym Improvements- Provide new clerestory windows on the east wall, new Terra Flex sports floor, paint walls and ceilings, new wood panel wall on west elevation

Mechanical Reno Allowance – Rework existing HVAC to supply and exhaust new Lobby and Restrooms. New HVAC distribution to Gym

Re-Roof Scope (I Upper & 2 Lower Roofs) -Replace entire roof and insulation with new R30 insulation and 80mil PVC roofing

Metal Fascia -Replace Metal soffit and fascia 100%, existing framing to remain, replace any damaged members

Limited Ceiling Repair (25%) - Replace any water damaged ceilings after new roof is in place

Planter - Remove existing landscaping, repair, waterproof and cap planters

Exterior Masonry & Concrete Foundation Wall Repair – Tuckpointing for the entire building, repair/replace of damaged masonry, repair damaged foundations

ADA Toilets – Adjacent to the Lobby, provide (2) new ADA restrooms and a janitor's closet


Transformer & Switchgear- Replace the existing ComEd transformer with new exterior transformer, replace existing switchgear in the same location

ADA Ramp & Stairs- provide new ramps/stairs on 1st and 2nd floor to allow accessibility to all floor levels.


New Addition – Construct a vestibule addition with elevator to second floor and connection to existing storage area. Includes

Site Work - Mitigate flooding issues with area drains and new storm line at entrance areas, new concrete sidewalk where are drains installed and new hardscape at new entrance

## Phase



PHASE 1 SCOPE - GROUND FLOOR



PHASE 1 SCOPE - UPPER FLOOR

Mechanical Reno Allowance – Repair and rework existing HVAC to renovated and remodeled spaces

Renovation – Update finishes, including lighting, in existing offices to remain, corridors, fitness existing restrooms to remain and kitchenette.


Remodel –Newly constructed or significantly altered spaces such as Regional office, Lobby/ Gathering space, Reception, Local office, Club Rooms, Dance Studio and Performance Space

Optional but Recommended MEP – Install Air Conditioning through out the building


Site Work - Rework the entrance from Clarendon for better street visibility and access, including new ramp and stairs. Provide a new outdoor gathering space in the Plaza along Clarendon, including a new at grade performance space with new landscaping.

Signage and Graphics- Includes interior signage and way finding, historical graphic display in the Lobby, Exterior signage including bird safe lighting for mosaic.

Replace Windows - Replace all exterior windows with energy efficient double glazed windows.



PHASE 2 SCOPE - GROUND FLOOR



PHASE 2 SCOPE - UPPER FLOOR

#### FLOOR 2 SCOPE DIAGRAM



#### Phase I Scope:

Gym Improvements

Re-Roof Scope Metal Fascia

Limited Ceiling Repair - 25%

Planter repairs

Masonry & Concrete & Foundation Wall Repair

ADA Toilets at Lobby

Transformer & Switchgear

Interior ADA Ramp & Stairs

**New Addition** 

Site Work

**Phase I Estimate** 

\$6,390,500

#### Phase 2 Scope:

Mechanical Allowance

Renovation Work

Remodel Work

Optional MEP Scope/ Air Conditioning

Site Work

Signage and Graphics

Window Replacement

**Phase 2 Estimate** 

\$8,460,170

Phase I and 2 total Estimate - \$14,850,670

(FFE Allowance - \$660,000 not included)

Based on Opinion of Cost provided by CCS dated 9/17/19

